

ASBESTOS BUILDING

TYPICAL LOCATIONS FOR THE MOST COMMON ASBESTOS-CONTAINING MATERIALS

KEY

ROOF AND EXTERIOR WALLS

- 1 Roof sheets and tiles
- 2 Guttering and drainpipe
- 3 Wall cladding
- 4 Soffit/facia boards
- 5 Panel beneath window
- 6 Roofing felt and coating to metal wall cladding

BOILER, VESSELS AND PIPEWORK

- 7 Lagging on boiler, pipework, calorifier etc.
- 8 Damaged lagging and associated debris
- 9 Paper lining under non-asbestos pipe lagging
- 10 Gasket in pipe and vessel joints
- 11 Rope seal on boiler access hatch and between cast iron boiler sections
- 12 Paper lining inside steel boiler casing
- 13 Boiler flue

CEILING

- 14 Spray coating to ceiling, walls, beams/columns
- 15 Loose asbestos in ceiling/floor cavity
- 16 Tiles, slats, canopies and firebreaks above ceilings
- 17 Textured coatings and paints

INTERIOR WALLS/PANELS

- 18 Loose asbestos inside partition walls
- 19 Partition walls
- 20 Panel beneath window
- 21 Panel lining to lift shaft
- 22 Panelling to vertical and horizontal beams
- 23 Panel behind electrical equipment
- 24 Panel on access hatch to service riser
- 25 Panel lining service riser and floor
- 26 Heater cupboard around domestic boiler
- 27 Panel behind/under heater
- 28 Panel on or inside, fire door
- 29 Bath panel

FLOORING MATERIALS

- 30 Floor tiles, linoleum and paper backing, lining to suspended floor

AIR HANDLING SYSTEMS


- 31 Lagging
- 32 Gaskets
- 33 Anti-vibration gaiter

DOMESTIC APPLIANCES

- 34 Gaskets, rope seals and panels in domestic boilers
- 35 'Caposil' insulating blocks, panels, paper, string etc in domestic heater
- 36 String seals on radiators

OTHER

- 37 Fire blanket
- 38 Water tank
- 39 Brake/clutch lining



Note: This diagram does not show all possible uses and locations of asbestos materials. A detailed survey will be required to identify all asbestos materials present in a building.

Further information can be found in the HSE publication MDHS100 Surveying and sampling asbestos-containing material