



The construction of Senior Day Girls House, and extension of Sports Pavilion

Project Title	New accommodation, and extension to existing Pavilion.
Location	Dauntsey's School
Client	Mr S Lilley - Bursar of Dauntsey's School
Architect / Contract Administrator	NVB Architects
Contract Value	£727,984
Duration of Works	49 Weeks
Completion	18th June 2009
Procurement Method	Open Tender
Contract No.	1535

The work comprised construction of a single storey accommodation building, and the refurbishment and extension of the existing cricket pavilion. The accommodation building comprised a timber-framed superstructure built off a piled ring and beam foundation, with internal plasterboard and plastered walls; and externally, either brickwork or cedar cladding. The building comprised six common rooms, two of which had sound proof dividing screens, three WCs, reception area, social areas and three offices. The cricket pavilion was extended either end and to the rear to create larger changing facilities. Strip foundations were used, with high substructure walls to meet the raised floor. The timber-framed superstructure was both externally and internally clad to match the existing building.